

Mount Analysis Summary - TXAD0405 Uptown Plaza

Prepared by Meridian Structural Engineering (synthetic) for Ericsson. SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	MA-TXAD0405-R0
Date	2026-09-06
Mount type	Roof sled mounts (non-penetrating)
Governing standard	TIA-222-H
Result	PASS
Mount capacity (proposed loading)	78%

No mount modifications required for the proposed loading.

Proposed appurtenance loading analysed

Sector	Pos	Equipment	Action	RC (ft)
Alpha	1	NNH4-65B-R6	Retain	63
Alpha	1	Radio 4449 B5 B12	Retain	63
Alpha	1	Radio 4460 B2 B66	Retain	63
Alpha	2	NNH4-65B-R6	Add	63
Alpha	2	Radio 4480 B71 B85	Add	63
Alpha	3	AIR 6419 B41	Add	68
Beta	1	NNH4-65B-R6	Retain	63
Beta	1	Radio 4449 B5 B12	Retain	63
Beta	1	Radio 4460 B2 B66	Retain	63
Beta	2	NNH4-65B-R6	Add	63
Beta	2	Radio 4480 B71 B85	Add	63
Beta	3	AIR 6419 B41	Add	68

Structural Analysis Summary - TXAD0405 Uptown Plaza

Prepared by Meridian Structural Engineering (synthetic). SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	SA-TXAD0405-R0
Date	2026-09-06
Structure	60 ft Rooftop
Owner	Uptown Plaza Holdings (building owner)
Governing standard	TIA-222-H, ASCE 7-16
Result	PASS
Controlling member capacity	81%

The structure has adequate capacity for the proposed loading.