

Mount Analysis Summary - TXCA0977 Carrollton Station

Prepared by Meridian Structural Engineering (synthetic) for Ericsson. SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	MA-TXCA0977-R0
Date	2026-09-07
Mount type	Existing 12 ft sector frames
Governing standard	TIA-222-H
Result	PASS WITH MODIFICATIONS
Mount capacity (proposed loading)	101%
Capacity after modifications	88%

Required modifications

Sector	Modification	Qty
Alpha	Install mount reinforcement kit (MRK-12) per detail S-2	1

Proposed appurtenance loading analysed

Sector	Pos	Equipment	Action	RC (ft)
Alpha	1	NNH4-65B-R6	Retain	105
Alpha	1	Radio 4449 B5 B12	Retain	105
Alpha	1	Radio 4460 B2 B66	Retain	105
Alpha	2	APXVSPP18-C-A20	Retain	105
Alpha	2	Radio 2217 B66A	Retain	105
Alpha	3	AIR 6449 B77D	Add	98
Beta	1	NNH4-65B-R6	Retain	105
Beta	1	Radio 4449 B5 B12	Retain	105
Beta	1	Radio 4460 B2 B66	Retain	105
Beta	2	APXVSPP18-C-A20	Retain	105
Beta	2	Radio 2217 B66A	Retain	105
Beta	3	AIR 6449 B77D	Add	98
Gamma	1	NNH4-65B-R6	Retain	105
Gamma	1	Radio 4449 B5 B12	Retain	105
Gamma	1	Radio 4460 B2 B66	Retain	105
Gamma	2	APXVSPP18-C-A20	Retain	105
Gamma	2	Radio 2217 B66A	Retain	105
Gamma	3	AIR 6449 B77D	Add	98

Structural Analysis Summary - TXCA0977 Carrollton Station

Prepared by Meridian Structural Engineering (synthetic). SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	SA-TXCA0977-R0
Date	2026-09-07
Structure	110 ft Monopole
Owner	BluePeak Towers
Governing standard	TIA-222-H, ASCE 7-16
Result	PASS
Controlling member capacity	81%

The structure has adequate capacity for the proposed loading.