

# RF DATA SHEET - CARRIER-A | TXCA0977 Carrollton Station | R3

SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION

| Field     | Value                           | Field                 | Value               |
|-----------|---------------------------------|-----------------------|---------------------|
| Site ID   | TXCA0977                        | Longitude             | -96.8903            |
| Site Name | Carrollton Station              | Structure Type        | Monopole            |
| Market    | DFW                             | Structure Height (ft) | 110                 |
| Customer  | CARRIER-A                       | Structure Owner       | BluePeak Towers     |
| Address   | 1900 E Belt Line Rd (synthetic) | Project Type          | 5G C-band add       |
| City      | Carrollton                      | RFDS Revision         | R3                  |
| State     | TX                              | RFDS Date             | 2026-08-10          |
| ZIP       | 75006                           | RF Engineer           | M. Chen (synthetic) |
| Latitude  | 32.9537                         |                       |                     |

## EXISTING CONFIGURATION

| Sector | Az  | Pos | Action   | Antenna / AAU   | RC (ft) | M-Tilt | E-Tilt | Radios (action)                                        | Bands         |
|--------|-----|-----|----------|-----------------|---------|--------|--------|--------------------------------------------------------|---------------|
| Alpha  | 45  | 1   | Existing | NNH4-65B-R6     | 105     | 0      | 6/4    | Radio 4449 B5 B12 (Retain), Radio 4460 B2 B66 (Retain) | B5/B12/B2/B66 |
| Alpha  | 45  | 2   | Existing | APXVSPP18-C-A20 | 105     | 2      | 6/6    | Radio 2217 B66A (Retain)                               | B66           |
| Beta   | 165 | 1   | Existing | NNH4-65B-R6     | 105     | 0      | 3/3    | Radio 4449 B5 B12 (Retain), Radio 4460 B2 B66 (Retain) | B5/B12/B2/B66 |
| Beta   | 165 | 2   | Existing | APXVSPP18-C-A20 | 105     | 2      | 4/3    | Radio 2217 B66A (Retain)                               | B66           |
| Gamma  | 285 | 1   | Existing | NNH4-65B-R6     | 105     | 2      | 2/2    | Radio 4449 B5 B12 (Retain), Radio 4460 B2 B66 (Retain) | B5/B12/B2/B66 |
| Gamma  | 285 | 2   | Existing | APXVSPP18-C-A20 | 105     | 1      | 3/3    | Radio 2217 B66A (Retain)                               | B66           |

## FINAL CONFIGURATION

| Sector | Az  | Pos | Action | Antenna / AAU   | RC (ft) | M-Tilt | E-Tilt | Radios (action)                                        | Bands         |
|--------|-----|-----|--------|-----------------|---------|--------|--------|--------------------------------------------------------|---------------|
| Alpha  | 45  | 1   | Retain | NNH4-65B-R6     | 105     | 0      | 6/4    | Radio 4449 B5 B12 (Retain), Radio 4460 B2 B66 (Retain) | B5/B12/B2/B66 |
| Alpha  | 45  | 2   | Retain | APXVSPP18-C-A20 | 105     | 2      | 6/6    | Radio 2217 B66A (Retain)                               | B66           |
| Alpha  | 45  | 3   | Add    | AIR 6449 B77D   | 98      | 1      | 6/3    | Integrated                                             | n77           |
| Beta   | 165 | 1   | Retain | NNH4-65B-R6     | 105     | 0      | 3/3    | Radio 4449 B5 B12 (Retain), Radio 4460 B2 B66 (Retain) | B5/B12/B2/B66 |
| Beta   | 165 | 2   | Retain | APXVSPP18-C-A20 | 105     | 2      | 4/3    | Radio 2217 B66A (Retain)                               | B66           |
| Beta   | 165 | 3   | Add    | AIR 6449 B77D   | 98      | 0      | 5/2    | Integrated                                             | n77           |
| Gamma  | 285 | 1   | Retain | NNH4-65B-R6     | 105     | 2      | 2/2    | Radio 4449 B5 B12 (Retain), Radio 4460 B2 B66 (Retain) | B5/B12/B2/B66 |
| Gamma  | 285 | 2   | Retain | APXVSPP18-C-A20 | 105     | 1      | 3/3    | Radio 2217 B66A (Retain)                               | B66           |
| Gamma  | 285 | 3   | Add    | AIR 6449 B77D   | 98      | 2      | 2/5    | Integrated                                             | n77           |

**BASEBAND & POWER**

| Item              | Model         | Action | Qty  |
|-------------------|---------------|--------|------|
| Baseband          | Baseband 6648 | Add    | 1    |
| Router            | Router 6675   | Retain | 1    |
| DC load added (W) |               |        | 3300 |

**REVISION HISTORY**

| Rev | Date       | Description            |
|-----|------------|------------------------|
| R1  | 2026-06-21 | Preliminary            |
| R2  | 2026-07-13 | Band plan update       |
| R3  | 2026-08-10 | Final for construction |