

Mount Analysis Summary - TXFW2217 Fossil Creek

Prepared by Meridian Structural Engineering (synthetic) for Ericsson. SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	MA-TXFW2217-R0
Date	2026-08-28
Mount type	Existing 12 ft sector frames
Governing standard	TIA-222-H
Result	PASS
Mount capacity (proposed loading)	78%

No mount modifications required for the proposed loading.

Proposed appurtenance loading analysed

Sector	Pos	Equipment	Action	RC (ft)
Alpha	1	NNH4-65B-R6	Retain	175
Alpha	1	Radio 4449 B5 B12	Retain	175
Alpha	1	Radio 4460 B2 B66	Retain	175
Alpha	2	APXVSPP18-C-A20	Retain	175
Alpha	2	Radio 2217 B66A	Retain	175
Alpha	3	AIR 6449 B77D	Add	168
Beta	1	NNH4-65B-R6	Retain	175
Beta	1	Radio 4449 B5 B12	Retain	175
Beta	1	Radio 4460 B2 B66	Retain	175
Beta	2	APXVSPP18-C-A20	Retain	175
Beta	2	Radio 2217 B66A	Retain	175
Beta	3	AIR 6449 B77D	Add	168
Gamma	1	NNH4-65B-R6	Retain	175
Gamma	1	Radio 4449 B5 B12	Retain	175
Gamma	1	Radio 4460 B2 B66	Retain	175
Gamma	2	APXVSPP18-C-A20	Retain	175
Gamma	2	Radio 2217 B66A	Retain	175
Gamma	3	AIR 6449 B77D	Add	168

Structural Analysis Summary - TXFW2217 Fossil Creek

Prepared by Meridian Structural Engineering (synthetic). SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	SA-TXFW2217-R0
Date	2026-08-28
Structure	180 ft Self-support tower
Owner	Trinity Structures
Governing standard	TIA-222-H, ASCE 7-16
Result	PASS
Controlling member capacity	81%

The structure has adequate capacity for the proposed loading.