

# Mount Analysis Summary - TXGR0719 Arbor Bend

Prepared by Meridian Structural Engineering (synthetic) for Ericsson. SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

| Item                              | Value                              |
|-----------------------------------|------------------------------------|
| Report                            | MA-TXGR0719-R0                     |
| Date                              | 2026-08-31                         |
| Mount type                        | New 12 ft sector frames (proposed) |
| Governing standard                | TIA-222-H                          |
| Result                            | PASS                               |
| Mount capacity (proposed loading) | 78%                                |

No mount modifications required for the proposed loading.

## *Proposed appurtenance loading analysed*

| Sector | Pos | Equipment         | Action | RC (ft) |
|--------|-----|-------------------|--------|---------|
| Alpha  | 1   | NNH4-65B-R6       | Add    | 190     |
| Alpha  | 1   | Radio 4449 B5 B12 | Add    | 190     |
| Alpha  | 1   | Radio 4460 B2 B66 | Add    | 190     |
| Alpha  | 2   | AIR 6449 B77D     | Add    | 190     |
| Alpha  | 3   | AIR 6419 B41      | Add    | 190     |
| Beta   | 1   | NNH4-65B-R6       | Add    | 190     |
| Beta   | 1   | Radio 4449 B5 B12 | Add    | 190     |
| Beta   | 1   | Radio 4460 B2 B66 | Add    | 190     |
| Beta   | 2   | AIR 6449 B77D     | Add    | 190     |
| Beta   | 3   | AIR 6419 B41      | Add    | 190     |
| Gamma  | 1   | NNH4-65B-R6       | Add    | 190     |
| Gamma  | 1   | Radio 4449 B5 B12 | Add    | 190     |
| Gamma  | 1   | Radio 4460 B2 B66 | Add    | 190     |
| Gamma  | 2   | AIR 6449 B77D     | Add    | 190     |
| Gamma  | 3   | AIR 6419 B41      | Add    | 190     |

# Structural Analysis Summary - TXGR0719 Arbor Bend

Prepared by Meridian Structural Engineering (synthetic). SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

| Item                        | Value                     |
|-----------------------------|---------------------------|
| Report                      | SA-TXGR0719-R0            |
| Date                        | 2026-08-31                |
| Structure                   | 195 ft Self-support tower |
| Owner                       | Trinity Structures        |
| Governing standard          | TIA-222-H, ASCE 7-16      |
| Result                      | FAIL                      |
| Controlling member capacity | 103%                      |

The structure does not have adequate capacity for the proposed loading. A structural modification design is required before installation.