

Mount Analysis Summary - TXPL0588 Legacy Drive

Prepared by Meridian Structural Engineering (synthetic) for Ericsson. SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	MA-TXPL0588-R0
Date	2026-08-29
Mount type	Existing 12 ft sector frames
Governing standard	TIA-222-H
Result	PASS WITH MODIFICATIONS
Mount capacity (proposed loading)	104%
Capacity after modifications	92%

Required modifications

Sector	Modification	Qty
Alpha	Install mount reinforcement kit (MRK-12) per detail S-2	1
Beta	Install mount reinforcement kit (MRK-12) per detail S-2	1
Gamma	Install mount reinforcement kit (MRK-12) per detail S-2	1

Proposed appurtenance loading analysed

Sector	Pos	Equipment	Action	RC (ft)
Alpha	1	NNH4-65B-R6	Retain	120
Alpha	1	Radio 4449 B5 B12	Retain	120
Alpha	1	Radio 4460 B2 B66	Retain	120
Alpha	2	NNH4-65B-R6	Add	120
Alpha	2	Radio 4480 B71 B85	Add	120
Alpha	3	AIR 6419 B41	Add	113
Beta	1	NNH4-65B-R6	Retain	120
Beta	1	Radio 4449 B5 B12	Retain	120
Beta	1	Radio 4460 B2 B66	Retain	120
Beta	2	NNH4-65B-R6	Add	120
Beta	2	Radio 4480 B71 B85	Add	120
Beta	3	AIR 6419 B41	Add	113
Gamma	1	NNH4-65B-R6	Retain	120
Gamma	1	Radio 4449 B5 B12	Retain	120
Gamma	1	Radio 4460 B2 B66	Retain	120
Gamma	2	NNH4-65B-R6	Add	120
Gamma	2	Radio 4480 B71 B85	Add	120
Gamma	3	AIR 6419 B41	Add	113

Structural Analysis Summary - TXPL0588 Legacy Drive

Prepared by Meridian Structural Engineering (synthetic). SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	SA-TXPL0588-R0
Date	2026-08-29
Structure	125 ft Monopole
Owner	Lonestar Tower Partners
Governing standard	TIA-222-H, ASCE 7-16
Result	PASS
Controlling member capacity	81%

The structure has adequate capacity for the proposed loading.