

Mount Analysis Summary - TXRI0906 Collins Tower

Prepared by Meridian Structural Engineering (synthetic) for Ericsson. SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	MA-TXRI0906-R0
Date	2026-09-04
Mount type	Roof sled mounts (non-penetrating)
Governing standard	TIA-222-H
Result	PASS
Mount capacity (proposed loading)	78%

No mount modifications required for the proposed loading.

Proposed appurtenance loading analysed

Sector	Pos	Equipment	Action	RC (ft)
Alpha	1	NNH4-65B-R6	Retain	91
Alpha	1	Radio 4449 B5 B12	Retain	91
Alpha	1	Radio 4460 B2 B66	Retain	91
Alpha	2	APXVSPP18-C-A20	Retain	91
Alpha	2	Radio 2217 B66A	Retain	91
Alpha	3	AIR 6449 B77D	Add	93
Beta	1	NNH4-65B-R6	Retain	91
Beta	1	Radio 4449 B5 B12	Retain	91
Beta	1	Radio 4460 B2 B66	Retain	91
Beta	2	APXVSPP18-C-A20	Retain	91
Beta	2	Radio 2217 B66A	Retain	91
Beta	3	AIR 6449 B77D	Add	93
Gamma	1	NNH4-65B-R6	Retain	91
Gamma	1	Radio 4449 B5 B12	Retain	91
Gamma	1	Radio 4460 B2 B66	Retain	91
Gamma	2	APXVSPP18-C-A20	Retain	91
Gamma	2	Radio 2217 B66A	Retain	91
Gamma	3	AIR 6449 B77D	Add	93
Delta	3	AIR 6449 B77D	Add	93

Structural Analysis Summary - TXRI0906 Collins Tower

Prepared by Meridian Structural Engineering (synthetic). SYNTHETIC SAMPLE - NOT FOR CONSTRUCTION.

Item	Value
Report	SA-TXRI0906-R0
Date	2026-09-04
Structure	85 ft Rooftop
Owner	Collins Tower LLC (building owner)
Governing standard	TIA-222-H, ASCE 7-16
Result	PASS
Controlling member capacity	81%

The structure has adequate capacity for the proposed loading.